

Consulting Services

- Troubleshooting in existing plants: assessment of actual process performance for aspects of gas and water quality, environmental requirements and demand of maintenance
- Bottleneck identification with recommendations for improvement
- Definition and ranking of measures to overcome the identified limitations of the investigated equipment
- Strategy plan detailling short, medium and long term measures: modification of operation procedures, equipment modification and optimization, recommendation of new equipment
- Feasibility study for green-field projects as well as brown-field projects - new equipment, revamping or refurbishment of complete by-product plants or parts thereof
- Pre-Engineering with process definition

Basic & Detail Engineering

- Project management
- Basic engineering: process definition, specification of equipment, layout planning, also in 3D
- Static calculation of plant equipment
- Safety analysis
- Detailed Engineering: Equipment drawings, automation and I&C-planning, engineering of pipeworks

Supply - Erection - Supervision of Erection and Commissioning

- Supply of key equipment as well as process equipment
- Supply of complete by-product plants in cooperation with partners
- Delivery to site
- Erection of delivered supply
- Supervision services for erection and commissioning of equipment delivered by DMT as well as equipment delivered by other parties

COKE OVEN GAS TECHNOLOGY Next Generation Technologies



Serving the World's Natural Resources Sector

DMT GmbH & Co. KG Industrial Engineering, Coke Oven Gas Technology Am TÜV 1, 45307 Essen, Germany

Tel +49 201 172 - 1590 Fax +49 201 172 - 1241

ine@dmt-group.com www.dmt-group.com



DIN EN ISO 9001 zertifiziert

DIN EN ISO 14001 zertifiziert

Earth. Insight. Values.



By-Product Plant at Coke Plant Ceara, Brazil

Design of the following Units of a complete By-product Plant for 88.000 Nm³/h coke oven gas:

- Primary gas cooler
- Electrostatic tar precipitator
- Gas exhauster
- Ammonia and hydrogen sulfide scrubbing system
- BTX scrubber
- Ammonia still and de-acidifier
- Wash oil regeneration plant
- Caustic soda dosing unit
- Crude benzene storage

Contract includes:

- Basic engineering of the mentioned units in the by-product plant
- Delivery of the key components for the process
- Erection supervision and commissioning

This Project is accomplished in Partnership with Paul Wurth Italia S.p.A., Italy

Replacement of a Primary Gas Cooler at Coke Plant Bottrop, Germany

Design and Delivery of a Primary Gas Cooler Replacement of Equipment in an existing plant during Operation

Primary gas cooler

Contract includes:

- Basic and detail engineering
- Delivery of gas cooler
- Erection
- Supervision
- Commissioning
- (Turn Key)

By-product Plant at Coke Plant Bhilai, India

Design of the following Units of a complete By-product Plant for 55.000 Nm³/h coke oven gas:

- Tar separation
- Primary gas cooler
- Electrostatic tar precipitator
- Gas exhauster
- Ammonia and hydrogen sulfide scrubbing system
- Naphtalene scrubber
- Gravel filter
- Claus plant
- Ammonia still and de-acidifier, wash oil regeneration

Contract includes:

- Basic and detail engineering
- Delivery of key components for the processs
- Erection supervision and commissioning

This Project is accomplished in Partnership with McNally Bharat Engg., India